



VALUE ADDED COATING SOLUTION PVT LTD

Office: 515, Devika Tower, Chander Nagar, Ghaziabad, 201010

Manufacturing: K-288, Site-V, Kasna, Greater Noida (U.P.)- 201310

+91- 9811846214 | +91- 9811357749 | info@coating-solution.com

www.optifinish.in | www.coating-solution.com



Techno-Commercial Offer

For

SARKAR ENTERPRISES, KOLKATA

POWDER COATING PLANT

13th October 2024





VALUE ADDED COATING SOLUTION PVT LTD

Office: 515, Devika Tower, Chander Nagar, Ghaziabad, 201010

Manufacturing: K-288, Site-V, Kasna, Greater Noida (U.P.)- 201310

+91- 9811846214 | +91- 9811357749 | info@coating-solution.com

www.optifinish.in | www.coating-solution.com



M/S SARKAR ENTERPRISES, KOLKATA

Kind Attn. : Mr. Prabir Sarkar Ji

Subject : Your Requirement of "POWDER COATING PLANT"

Reference : As per discussion with you.

Dear Sir,

We thank you for the courtesy and interest shown in our organization & products. Further based on the discussion held with you and based on the technical data provided by you, we are submitting our Techno-Commercial proposal for the subject captioned above.

We hope you will find our technical offer meeting with your requirements and you will favour us with your valuable Order.

Please feel free to contact us for further clarifications, if any.

Look forward your valuable Order at the earliest.

Thanking You

Yours faithfully,
For **Value Added Coating Solution Pvt. Ltd.**

HARISH SHARMA

Mob: (+91) 9319086612

Email: sales@optifinish.in



VALUE ADDED COATING SOLUTION PVT LTD

Office: 515, Devika Tower, Chander Nagar, Ghaziabad, 201010

Manufacturing: K-288, Site-V, Kasna, Greater Noida (U.P.)- 201310

+91- 9811846214 | +91- 9811357749 | info@coating-solution.com

www.optifinish.in | www.coating-solution.com



TABLE OF CONTENTS

1	VALUE ADDITION WITH VACSPL	4
2	SCOPE OF SUPPLY	4
3	TECHNICAL DESCRIPTION OF POWDER COATING PLANT	4
3.1	POWDER CURING OVEN WITH AIR SEAL DESIGN	4
3.2	MATERIAL HANDLING OVER HEAD CONVEYOR SYSTEM	6
3.3	ELECTRICAL CONTROL PANEL	6
4	COMMERICAL OFFER FOR POWDER COATING PLANT	7
5	DELIVERY & PAYMENT TERMS	7
6	EXCLUSIONS	8
7	UTILITY PROVIDED BY CUSTOMER	9



VALUE ADDED COATING SOLUTION PVT LTD

Office: 515, Devika Tower, Chander Nagar, Ghaziabad, 201010

Manufacturing: K-288, Site-V, Kasna, Greater Noida (U.P.)- 201310

+91- 9811846214 | +91- 9811357749 | info@coating-solution.com

www.optifinish.in | www.coating-solution.com



1 VALUE ADDITION WITH VACSPL

- Leader & Legend - VACSPL pioneered the powder coating technology in India.
- Constant efforts towards developing better technology in surface coating at our R & D base.
- Easy availability of spares assures continuous production.
- Prompt service from our sales and service offices at Ghaziabad, Gurgaon and Rudrapur, who are technically competent to handle any eventuality.

2 SCOPE OF SUPPLY

S. No.	Item	Unit
1.	Powder Curing Oven with Air Seal Design	01 Set
2.	Material Handling Overhead Conveyor	01 Set
3.	Electrical Control Panel with Field Wiring	01 Set
4.	Erection & Commissioning	01 Job

3 TECHNICAL DESCRIPTION OF POWDER COATING PLANT

3.1 POWDER CURING OVEN WITH AIR SEAL DESIGN

S. No.	Item	Description
1.	Qty.	01 Set
2.	Process	Powder Curing
3.	Type	Straight Conveyorized Oven (ground mounted)
4.	Entry type	Air Seal Design
5.	Heating source	Indirect GAS fired system
6.	Design Temperature	220 °C
7.	Working temperature	180-200 °C
8.	Temperature controller	Digital single set point ON/OFF control with PT-100 sensor
9.	Heating zone length	20000 mm. approx..
10.	Air seal length	1500 mm. each
11.	Overall dimensions	23600 x 1600 x 3500 mm (L, W, H) approx.
12.	Curing schedule	EMT – 12~13 min @ 180 °C Heating zone residence time – 20 min @200 °C
13.	Construction type	Male-Female type GI Insulated Panels with stiffeners



VALUE ADDED COATING SOLUTION PVT LTD

Office: 515, Devika Tower, Chander Nagar, Ghaziabad, 201010

Manufacturing: K-288, Site-V, Kasna, Greater Noida (U.P.)- 201310

+91- 9811846214 | +91- 9811357749 | info@coating-solution.com

www.optifinish.in | www.coating-solution.com



14.	Panel thickness	1.20 mm
15.	Heating zone residence Time	20 Minutes@ Speed of 1.0 metre/minute
16.	Thermal insulation	200 mm thick Rockwool slabs (resin bonded) having 96 kg/cum density, duly fitted; silicon sealant applied between the panel joints.
17.	Heat exchanger location	Side of the oven
18.	Heat exchanger type	Indirect
19.	MOC of heat exchanger	SS-304
20.	Initial Heat Load	2,40,000 Kcal./hr
21.	Running Heat Load	2,00,000 Kcal./hr
22.	Burner capacity	3,20,000 Kcal./hr
23.	Burner make	Eco flame
24.	Hot air circulation fan	Reverse blade type, V-belt driven duly protected with fan casing for proper in directional flow of air.
25.	HAC fan capacity	31,500 cmh, 70 mm head, 01 Nos.
26.	Motor capacity	22.5 KW, 01 Nos.
27.	No. of air seal	02
28.	Air seal fan type	V-belt driven centrifugal fan
29.	Air seal fan capacity	6,900 cmh, 40 mm head, 02 Nos.
30.	Motor capacity	2.25 KW, 02 Nos.
31.	Air delivery duct	Shall be provided at the bottom of the oven throughout its cross section. The duct shall have properly placed louvers to get the uniform air all through the oven.
32.	Fresh Air Filter	01 Nos.
33.	Type of Filter	Glass wool Filter
34.	No. of Canopy	02 Nos.
35.	Blower for Canopy	N/A (Natural Draft Only)
36.	Safety Interlock	Shall be provided for blower & burner
37.	Painting	One coat of primer followed by finish synthetic enamel paint



VALUE ADDED COATING SOLUTION PVT LTD

Office: 515, Devika Tower, Chander Nagar, Ghaziabad, 201010
Manufacturing: K-288, Site-V, Kasna, Greater Noida (U.P.)- 201310
+91- 9811846214 | +91- 9811357749 | info@coating-solution.com
www.optifinish.in | www.coating-solution.com



3.2 MATERIAL HANDLING OVER HEAD CONVEYOR SYSTEM

S. No.	Item	Description
1.	Qty.	85 meters approx.
2.	Type of Conveyor	4-W Overhead conveyor
3.	Model of Conveyor	E-con Super 10
4.	Chain Link Pitch	254 mm
5.	Hanging Pitch	508 mm & it's multiple
6.	Component Pitch	7,200 mm approx..
7.	Max. weight Per hanger	50 kg
8.	Speed	1.0 Meter/Minute (Variable by VFD)
9.	Drive unit	Caterpillar type
10.	Lubrication Unit	Air Mist Lubricator type
11.	Tensioning Unit Set	Screw Type
12.	Overload Safety	Mechanical shear pin arrangement
13.	Supporting structure	The conveyor will be supported from ground
14.	Paint and finishing	The track will be Orange
15.	Control Panel	440-volt AC with Linear speed indicator & VFD
16.	Motor protection	Over load relay for High current in Control panel and Thermostat to trip Motor at High temperature.

3.3 ELECTRICAL CONTROL PANEL

The Control Panel consists of controls for Powder Curing Oven, Conveyor & all other electromechanical equipment supplied in the complete Powder Coating Plant. The Cabinet is made up of MS Sheets duly powder coated & supported by suitable structure.

All supplied items will be of reputed makes. The Controls will be as follows:

- Mains On/Off Switch Fuse Unit
- Blower motors Start/ Stop with 'ON' Indication & 3 Pole MCBS
- Voltmeter & Ammeter with selector switch
- Temperature indicators cum controllers for Oven & Flue Gas Temperature
- Burner Start / Stop with ON Indication & ON Delay Timer
- Motor Protection Relays
- Emergency Stop
- Interlocks between oven blower & burner
- Interconnections



VALUE ADDED COATING SOLUTION PVT LTD

Office: 515, Devika Tower, Chander Nagar, Ghaziabad, 201010

Manufacturing: K-288, Site-V, Kasna, Greater Noida (U.P.)- 201310

+91- 9811846214 | +91- 9811357749 | info@coating-solution.com

www.optifinish.in | www.coating-solution.com



Note:

1. Incoming & Outgoing cables from top side of control panel.
2. Cabinet will be powder coated in Siemens Grey & Bottom frame in black color.
3. For Blower Star/Delta Starters are considered.
4. Cables will be laid overhead in suitable cable trays with proper supports wherever necessary.
5. All Switchgear/Contactors/Pushbuttons will be of Siemens make.
6. For control panels minimum clearance of 1000 mm is recommended from all sides.
7. Mains Supply Considered – 3 phase, 4 wire with Neutral 400 V AC, 50 Hz. (Same to be provided by Customer)
8. Proper Earthing to control Panel (Same to be provided by Customer)

4 COMMERCIAL OFFER FOR POWDER COATING PLANT

S. No.	ITEM DESCRIPTION	UOM	BOM		AMOUNT
1.	POWDER CURING OVEN WITH AIR SEAL DESIGN	SET	1	INR	29,95,000
2.	MATERIAL HANDLING CONVEYOR SYSTEM	SET	1	INR	10,45,000
3.	ELECTRICAL CONTROL PANEL & FIELD WIRING	SET	1	INR	2,85,000
4.	ERECTION & COMMISSIONING	JOB	1	INR	4,00,000
TOTAL PROJECT COST				INR	47,25,000

5 DELIVERY & PAYMENT TERMS

1.	Price Basis	Ex works, Noida
2.	Freight	Extra
3.	Packing (If required)	Included
4.	Transit Insurance	Extra
5.	GST	Extra
6.	Delivery	15-17 weeks from the date of PO with advance
7.	Erection	8-10 weeks



VALUE ADDED COATING SOLUTION PVT LTD

Office: 515, Devika Tower, Chander Nagar, Ghaziabad, 201010

Manufacturing: K-288, Site-V, Kasna, Greater Noida (U.P.)- 201310

+91- 9811846214 | +91- 9811357749 | info@coating-solution.com

www.optifinish.in | www.coating-solution.com



8.	Commissioning	2-3 weeks
9.	Advance along with PO	50%
10.	Against Inspection (PI)	40% Basic + 100% Taxes
11.	Against Commissioning	10%
12.	Delivery Condition	Dismantle, partly pre-assembled.
13.	Warranty	18 months from the date of Supply or 12 months from date of commissioning whichever is earlier.
14.	Limitation	Our liability limited to design, manufacture and supply and installation of Plant as per enclosed scope and specs.
15.	Deserve to modification	We reserve the right to alter the plant design without Deteriorating the utility, performance and operating safety.
16.	Right of Reserve	This Quotation is the Sole Property of VACSPL and should not be handed over to Third Party without permission from VACSPL.
17.	Quotation Validity	15 days

6 EXCLUSIONS

- Civil Work
- Jig & Hangers
- All Chimney Structure
- Roof opening & Closing for Exhaust ducts.
- Air Supply for Auto Air Zone
- Pit for Drain, trench
- LPG pipe line with Filter and Regulator up to Burners.
- Incoming power Supply for Control panels with Earthing.
- Earthing at All panels, structure, Ovens separately
- Stands for Jigs/Fixture, Jigs
- Material moving Trolley
- Material Unloading/Shifting/Cranes at site.
- Materials shifting up to Shop floor.
- Platform for Fume Exhaust System
- Uniform floor level in Plant area - +/- 10 mm



VALUE ADDED COATING SOLUTION PVT LTD

Office: 515, Devika Tower, Chander Nagar, Ghaziabad, 201010

Manufacturing: K-288, Site-V, Kasna, Greater Noida (U.P.)- 201310

+91- 9811846214 | +91- 9811357749 | info@coating-solution.com

www.optifinish.in | www.coating-solution.com



- Free power at the time of Installation and commissioning.
- Shop floor lighting
- Floor painting
- Any other items required which are not stated in our offer.

7 UTILITY PROVIDED BY CUSTOMER

1. Electricity

- Power – 415 V + / - 5 %, 3 phase, 50 Hz + / - 2 %, 4 wire AC supply.
- Control – 230 V + / - 5 %, single phase, 50 Hz + / - %, 2 wire AC supply.

2. Compressed air of following quality and quantity

- Dirt – lum – 1 mg / N m 3 max.
- Water content – < 1.3 gm / Nm³; - 40 deg C p d p.
- Oil content – < 0.1 mg / Nm³.
- Pressure – @ 7 bar.
- Qty. Will be provided later.

3. Fuel for Heating System

- Type – LPG/Propane/NG (Client to confirm any one)

Note: Net calorific value of LPG considered 11500 Kcal/Kg Above fuel consumption figures are under worst ambient condition @ 7.5 °C

Notes:

1. Customer to provide above utilities free of cost during erection/trial/pre-commissioning/commissioning period.
2. All Utilities to be provided by client at the points required by VACSPL. All the control panels to be charged with MCCB and earthing to be provided by Client.

Note: The above values of utilities are tentative and may change during detail designing.



VALUE ADDED COATING SOLUTION PVT LTD

Office: 515, Devika Tower, Chander Nagar, Ghaziabad, 201010

Manufacturing: K-288, Site-V, Kasna, Greater Noida (U.P.)- 201310

+91- 9811846214 | +91- 9811357749 | info@coating-solution.com

www.optifinish.in | www.coating-solution.com



**THANK YOU
FOR ANY ENQUIRY PLEASE CONTACT**



Opti finish

HARISH SHARMA

Mobile: (+91) 9319086612

Email: sales@optifinish.in